

BID TAB



KING CREEK RECOVERY (FEMA)					
ITEM	SITE 01 KING TRAIL	QUANTITY	UNIT	UNIT COST	TOTAL COST
1	DEMO EXISTING REMAINING TRAIL	755.00	SY		\$0
2	SOIL PREPERATION (INCLUSIVE OF FINE GRADING AND COMPACTION)	1,058.00	SY		\$0
3	BASE COURSE (3"DEPTH AGGREGATE BASE COURSE(ABC))	132.23	TON		\$0
4	TREAD/SURFACE COURSE (3" DEPTH GRANITE FINES)	88.15	CY		\$0
ITEM	SITE 02 KING TRAIL				
5	DEMO EXISTING REMAINING TRAIL	186.00	SY		\$0
6	SOIL PREPERATION (INCLUSIVE OF FINE GRADING AND COMPACTION)	186.00	SY		\$0
7	BASE COURSE (3"DEPTH AGGREGATE BASE COURSE(ABC))	23.19	TON		\$0
8	TREAD/SURFACE COURSE (3" DEPTH GRANITE FINES)	15.46	CY		\$0
ITEM	SITE 03 KING CREEK - A) BRUSH PACK; B) BANKFULL BENCH	QUANTITY	UNIT		
9	DEMO-REMOVE DAMAGED TREE (B)	1.00	LS		\$0
10	DEMO-CUT HANGING CULVERT (B)	1.00	LS		\$0
11	CLEARING AND GRUBBING	0.02	AC		\$0
12	EARTHWORK (LAY BANK DOWN) (B)	416.00	CY		\$0
13	GEOTEXTILE (B)	185.00	SY		\$0
14	NATIVE FILL (A)	65.00	CY		\$0
15	WOODEN STAKES (A)	1.00	LS		\$0
ITEM	SITE 04 KING CREEK - BANKFULL BENCH	QUANTITY	UNIT		
16	EARTHWORK (LAY BANK DOWN)	480.00	CY		\$0
17	CLEARING AND GRUBBING	0.10	AC		\$0
18	GEOTEXTILE	495.00	SY		\$0
ITEM	SITE 05 - ENCAPSULATED SOIL LIFTS				
19	EARTHWORK (PULL BANK BACK, REPLACE WITH NATIVE SOIL LIFTS)	485	CY		\$0
20	CLEARING AND GRUBBING	0.02	AC		\$0
21	COIR BLOCKS	650	LF		\$0
22	GEOTEXTILE	1517	SY		\$0
23	WOODEN STAKES	1.00	LS		\$0
ITEM	SITE 06 - ENCAPSULATED SOIL LIFTS	QUANTITY	UNIT		
24	EARTHWORK (PULL BANK BACK, REPLACE WITH NATIVE SOIL LIFTS)	485	CY		\$0
25	COIR BLOCKS	650	LF		\$0
26	GEOTEXTILE	1517	SY		\$0
27	WOODEN STAKES	1.00	LS		\$0
ITEM	ALL	QUANTITY	UNIT		
28	MOBILIZATION (MOBILIZING AND DEMOBILIZING EQUIPMENT)	1	LS		\$0
29	EROSION CONTROL-TEMPORARY ACCESS AND HAUL ROAD & REMOVAL	9773	SY		\$0
30	EROSION CONTROL-TEMPORARY COIR LOG	583	LF		\$0
31	EROSION CONTROL-TEMPORARY SEED	0.7	AC		\$0
32	REINFORCED SILT FENCE	1,250	LF		\$0
33	LIVE STAKES	342	EA		\$0
34	NATIVE PLANTINGS - PLUGS	567	EA		\$0
35	PERMANENT SEED	0.13	AC		\$0
36	NATIVE PLANTINGS #1 POT	35	EA		\$0
37	NATIVE PLANTINGS - 1 GAL.	44	EA		\$0
38	NATIVE PLANTINGS - 2 GAL.	25	EA		\$0
39	NATIVE PLANTINGS - 3 GAL.	40	EA		\$0
40	NATIVE PLANTINGS - 10 GAL.	26	EA		\$0

BID TOTAL	\$0
------------------	------------

NOTES: Quantities provided are provided as a courtesy to aid in contractor takeoffs. If discrepancies are found between quantities provided and the plans, the plan sets shall take precedence. See plan sets for specifications for items listed.

1. Gravel (Base/surface course) figures do not account for gravel that may be stockpiled from existing location to be used.
2. Comprehensive grading take-offs include all cut and fill required for project.
3. All materials and structures listed includes materials and install (labor) per plans or manufacturer's specifications (whichever is listed).
4. Responsibility if the bidder to ensure tabs are calculating correctly